

# Bridge Structure Rehabilitation

---



## Field Application of Rapid Installation Method

**Anthony J. Lamanna**  
Assistant Professor

September 26, 2003

Department of Civil and  
Environmental Engineering  
Tulane University  
[lamanna@tulane.edu](mailto:lamanna@tulane.edu)



US Army Corps  
of Engineers



 Civil and Environmental  
Engineering

# Outline

---

Current Method

Rapid Method

Bridge Selection

Bridge Details

Design Details

Field Installation

Installation Observations

Service Load Test

Cost

Conclusions

# Current Method of Bonding FRP

---



## Negatives:

- Surface preparation
- Cure time
- Skilled labor





# Rapid Method of Attaching FRP

Rapid application


Simplified application

Minimal surface preparation

Application in adverse environments

Simplified design criteria

Ductile behavior of strengthened beam



# Bridge Selection

---



- Flat slab bridge
- Constructed in 1930
- Designed for H15 truck loading
- HS 17.6 inventory rating
- HS 29.3 operating rating
- 32.7 sufficiency rating
- Efflorescence on edge of slab
- Scheduled for replacement 2003



# Bridge Details


23 ft span

25.9 ft wide


Square bars

33,000 psi steel

Main reinforcing bent near abutments





# Design Details



**H15 to HS20 = 33% Increase**

**H15 to HS25 = 67% Increase**

# Design Details





# Field Installation

---



Strip supplied in 100 ft rolls

Cut to 21 ft 2 in. lengths

Fastener locations marked & pre-drilled

Work platform constructed under bridge

Soft calcium removed with putty knife



# Field Installation



Strip duct taped in position  
Midspan fastener installed  
Midspan to abutment, repeated  
15 minutes to position strip  
15 minutes to attach strip





# Field Installation

---



End Anchor Bolts




12" strip spacing



Strengthened bridge

# Installation Observations

---



Due to deterioration  
or poor consolidation



Over driven fastener



Out of plane variations



# Installation Observations

---



Strips relocated a few inches to avoid major damage



# Service Load Test

---



- 25.4 Tons

- Strains very small

(Strains reduced in some cases up to 88%)

- Strips left in place 1 year

- Service load test repeated

- Bridge tested to failure



# Cost

---

Total Cost (Materials + Labor) = \$7,995.00

Unit Cost = \$ 12.72 / ft<sup>2</sup>

(Existing Epoxy Bonded Systems cost well over \$25/ft<sup>2</sup>)

DOT Workers had no prior training

# Conclusions

---

1. Economical
2. Strips successfully attached to deteriorated concrete
3. Design calculations show increase from HS17 to HS25
4. Both stainless steel & galvanized fasteners install well
5. Service testing inconclusive



# Questions?

---

