

The Interconnection of the East and West Bank Water Supplies


St. Charles Parish Department of
Waterworks



St. Charles Parish



St. Charles Parish



St. Charles Parish Waterworks Districts

- Eastbank Waterworks District One
 - Created on November 17, 1949
- Westbank Waterworks District Two
 - Created on November 21, 1949
- Department of Waterworks
 - Created on November 6, 1989



WATER TREATMENT CAPACITY

- **EastBank Production Capacity - 7 MGD**

A Plant Built in 1950 (1.5 MGD)

B Plant Built in 1965 (1.5 MGD)

C Plant Built in 1978 (4 MGD)

- **WestBank Production Capacity - 9 MGD(+30%)**

A Plant Built in 1950 (1 MGD)

B Plant Built in 1963 (2 MGD)

C Plant Built in 1973 (3 MGD)

D Plant Built in 1983 (6 MGD) 3 MGD Filter Capacity



District #1 and #2 Consolidated

November 1989

- Under the River Connection first conceived shortly after consolidation
 - Directional Boring & HDPE still new to water industry
 - Deemed Cost Prohibitive
- Last Expansion of the East Bank Production Facilities was completed in 1978.
 - “C-Plant” Responsible for more than ½ of Daily Water Demand on the East Bank of St. Charles
 - Could not be taken out of service for long enough to repair without running out of water (approx. 18 hrs)




Katrina Effect


- Began Plant Expansion Engineering in 2003
- Hurricane Katrina caused extensive wind damage but no loss of water system
 - All leaks repaired in first weeks
 - No catastrophic flooding
 - Refugees from surrounding areas (60% increase on EB)
- Decide on two pronged approach to Capacity
 - Complete Design of Plant Expansion (\$\$\$)
 - Interconnection of East and West Bank Water (120)




Water Consumption



Water Consumption



Water Consumption



Design Criteria

- Proper Sizing of the Two Lines
 - Internal Pressures on Pipe –DR9 (150~156 lbs)
 - Over Burden Pressure (Service Load Condition 130 lbs)
 - Pulling Strength
- Proximity to Treatment Plant / Large Mains
 - Plants located 5 miles apart on river
 - #1 connected 16" EB main at Plant to 10" WB main
 - #2 connected 10" WB main to 12" EB main (16"WB south of UPRR)
- Sufficient Room for Layout
 - #1 - 3350 feet (.63 miles) #2 - 2957 feet (.56 miles)


Design Criteria

- Levee Slope Stability Control Line / Batture
 - WB of Crossing #1 had batture > 1900 ft. (permitted)
 - 30 ft from Toe of Levee
 - 25 ft below River Bottom
- Landowners / Servitudes
 - Multiple Owners
 - Business Impact Mitigation
- Soil Conditions
 - Hydrographic Survey for River Bottom Profile
- Distance Across River / Crossing Angles
- Temporary Access Roads / Weight Loading on Levee





PROJECT NO. 06-000000-0000-0000-0000




OCTOBER 2006



SHREAD-KUYKENDALL & ASSOC.
ENGINEERS-SURVEYORS-PLANNERS
BATON ROUGE, LOUISIANA

**ST. CHARLES PARISH SUB-AQUOUS
CROSSING NO. 1**

**VICINITY MAP
ST. CHARLES PARISH, LOUISIANA**




MAY 2006



SHREAD-KUYKENDALL & ASSOC.
ENGINEERS-SURVEYORS-PLANNERS
BATON ROUGE, LOUISIANA

MISSISSIPPI RIVER SUB-AQUEOUS
CROSSING NO. 2B

BORING SITE PLAN
ST. CHARLES PARISH, LOUISIANA



Permitting, etc.

- Louisiana Department of Transportation
 - Crossing LA 18 / LA 48 on both crossings
 - LA 3160
- Railroad Right of Way Permits
 - Illinois Central (Crossing #2a)
 - Union Pacific (Crossing #2b)
- Louisiana Department of Health and Hospitals
 - Office of Public Health
- Louisiana State Land Office (>\$10,000)
- U. S. Coast Guard



Permitting, etc.

- U.S. Army Corps of Engineers
 - Permits
 - Technical
 - Geotechnical Engineering
 - Structural Engineering
 - Mitigation
- Department of Natural Resources
 - Wetland Mitigation \$7K for #1 - \$36K for #2
- Pontchartrain Levee District
- Lafourche Levee District
- River Stage > 11 ft NGVD at Carrollton Gage
- Air Release / SCADA Controlled Valves / Flow Meters



Construction of Crossing #1

- Construction
 - Vermeer 330x500 directional drilling rig was used
 - 8" pilot hole took 4 1/2 days averaging 733 ft/day (11")
 - Backreaming pass made with 24-inch fly cutter
 - Second pass made with 36-inch fly cutter (16 Days)
 - Pullback of the Pipe took 10 hours (Max depth 150 feet)
 - Contained a compound curve of 6 degrees to the left and 9 degrees to the right to stay within acquired property
- Layout / Impact to State Highway (66 Joints of Pipe)
- Pressure Testing of High Density Polyethylene
 - Utilizing Air versus Water
 - Above / Below Ground









Passing Bacteriological Testing

- Debris in Line
 - Pigging Line to remove debris (Used 93)
 - Fused Joints (66 Total on Crossing #1)
 - Elevation / Slope of Pipe
- “Timing” samples to ensure complete Disinfection of water main
 - AWWA recommends sample taps ever 1000’
- Videoing Interior of the Main

MH inlet near
10/01/2008

TO
Joint 3

MH middle of
14:08

Camera Underwater
250.1 FT



MH inlet near
10/01/2008

TO

MH middle of
14:10


General Photo
250.1 FT




Rejecting / Redesign of Crossing #2

- Mississippi River Levee Slope Stability Line
- Acquiring land / Servitude
 - Land Purchase
 - Multiple Owners (11) with pipe at 45 degrees to property
- New Permits (Starting the Process Again)
 - USACOE
 - Pontchartrain and Lafourche Levee Boards
 - LDOTD
 - DNR
 - Louisiana State Land Office
 - LDHH







VICINITY MAP
ST. CHARLES PARISH, LOUISIANA

Constructing Crossing # 2

- Construction
 - 8" pilot hole took 3 days averaging 1000 ft/day (4")
 - Backreaming pass made with 24-inch fly cutter
 - Second pass made with 36-inch fly cutter (14 Days)
 - Pullback of the Pipe took 8 hours (Max depth 165 feet)
- Avoiding Construction Delays / Damages
 - Fusible Pulling Head
 - Filling the Line with Water Prior to Pull
 - Gashes in Pipe Wall / What is acceptable? 10%
 - Road Closures and their impact on community
 - Impacts to the Environment (Historic Oak Trees)
 - Impacts to local residents / businesses (RR Luling)















Benefits of Connections

Anticipated

- Reduce / Eliminate Dependence on outsiders
- Redundancy of Water Intakes
- Increasing Water Pressure / Flows
- Ability to use excess Capacity on West to Supplement East in the events that demand exceeded design capacity or with failure of East Bank C Plant
- Freeze Event (1.5 MGD to East)



Westbank Plant

Flow Trends



South Tranfer Line

2:08:11 PM
4/13/2010

ST

SR

MZ

BG

DA

T


NT

Daily Positive Flow
Daily Negative Flow
Weekly Positive Flow
Weekly Negative Flow

516722 GALLONS
-141 GALLONS
2874256 GALLONS
-141 GALLONS

Luling

100.0 %



Destrehan

100.0 %

562.5 GPM

| Ack | Time In | Tagname | Status | Value | Description |
|-----|--------------|--------------------|--------|-----------|----------------------------------------|
| ✓ | 14:30:04.328 | B3_4FILTER_LEVEL | LO | 10.7 | Filter B-3/4 Level |
| ✓ | 13:47:51.820 | DA_SYSTEM_DISARMED | CFN | DISARM | Des Allemands Security Alarm System On |
| ✓ | 08:29:43.300 | DISTNW | LOLO | 1 | Distribution Water Flow North West |
| ✓ | 08:09:45.968 | FRONT_GATE_CONTACT | CFN | GATE OPEN | |
| ✓ | 07:23:51.810 | TANK3 | LOLO | -0.3 | Storage Tank Level |
| ✓ | 06:54:28.300 | RAWA | LO | 93 | Raw Water Flow A Plant |



Benefits

More than Anticipated

- Ability to Balance Flows from Each Unit to Increase Efficiency
- WB D-Plant out of service at Peak Demand Season
- EB Distribution Mains at Plant rerouted with no issues to customers
- Changes throughout both Distribution Systems
- River Crossings vs. Storage Tanks
 - (1 Million Gallons = 4.8 Hours)

The Interconnection of the East and West Bank Water Supplies

Questions or Comments?

Robert Brou – Director of St. Charles Parish Waterworks
(985) 783-5110 rbrou@scpwater.org

Dondi Troxler – Assistant Director
(985) 783-5110 dtroxler@scpwater.org

Gary McClure, P.E. – Project Engineer Shread-Kuyrkendall & Assoc.
(225) 296-1335 gmcclure@skaengr.com

David A. Einsel, P.E. – Project Engineer Shread-Kuyrkendall & Assoc.
(225) 296-1335 deinsel@skaengr.com





